BANGALORE DIVISION.

Dated 28th February 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 5th March 1927, for Restoring Bidargere Doddakere Tank, Registered No. 29, Anekal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Bidargere Doddakere Tank, Registered No. 20, Anekal Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate for Restoring Bidargere Doddakere Tank, Registered No. 20 of Anekal Taluk.

No.	Item of work	Per	Quantity
	BUND.		
1	Earthwork raising bund to R. L. 55·00	C.yd.	7,032
2	Do cutting slopes	"	181
3	Removing and resetting old stone work with new jelly	"	591
4	New stone work	"	380
5	Jelly wedging to old stone revetment	"	248
6	Removing, refixing old grade stones after cutting figures and painting.	No.	17
7	Turfing	S.yd.	8,094
8	Preparing and fixing new grade stones including painting and figuring.	No.	13
9	Index stone	"	30
10	B. M. Stones painting and figuring old	"	2
11	Registered number stone (painting and figuring) old ...	Lumpsum	rupees
12	Gauge stones (new)	do	do
	SLUICE No. 1.		
1	Earthwork cutting bund for examining sluice and refilling with consolidation.	C.yd.	177
2	Repairing the leaks in the sluice and providing plug rod, etc., locking arrangement, etc., complete.	Lumpsum	rupees

No.	Item of work	Per	Quantity
	SLUICE No. II.		
1	Earthwork cut opening the bund and examining the sluice and refilling with watering and tamping, etc.	C.yd.	295
2	Blocking up old sluice with masonry, etc.... ...	Lumpsum	rupees
3	Surki concrete filling	C.ft.	302
4	Burnt brick in surki mortar	,,	394
5	Burnt stone slabs 6" thick roughly dressed ...	Sqr.	307
6	Plastering with surki	,,	3·81
7	Rough surki plaster	,,	2·34
8	Cement pointing	,,	0·53
9	Dressing and drilling orifice	No.	1
10	Providing plug with iron rod, etc., complete ...	Lumpsum	rupees
11	Dismantling old sluice	do	do
12	Forming ring bund and baling water	do	do
13	Removing and rebuilding old stone work	C.yd.	7
14	New stone work	,,	9
	WASTE WEIR No. 1 LEFT 46' LONG.		
1	Earthwork excavation in weir and using for flanks ...	C.yd.	163
2	Dismantling the existing up right and using as pin slabs	Lumpsum	rupees
3	Surki concrete	C.ft.	175
4	Burnt brick in surki mortar	,,	340
5	Burnt stone slabs 6" thick	S.ft.	245
6	Removing and resetting old stone work with new jelly	C.yd.	37
7	New stone work	,,	62
8	Plastering with surki	Sqr.	4·53
	WASTE WEIR No. II RIGHT.		
1	Earthwork	C.yd.	18
2	Surki concrete	C.ft.	35
3	Burnt brick in surki mortar	,,	125
4	Surki plastering	Sqr.	1·61
5	Cement plastering	,,	0·90
6	Rough stone work new	C.yd.	3
7	Do old	,,	2

Dated 28th February 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 7th March 1927, for Raising the waste weir of Suleri Tank, Registered No. 113 of Channapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit
	...	
	...	
	...	

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Raising the waste weir of Suleri Tank, Registered No. 113, Channapatna, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders wil be returned.

Detailed abstract estimate for Raising the waste weir of Suleri Tank by one foot, Registered No. 113 of Channapatna Taluk.

No.	Item of work	Per	Quantity
	BUND.		
1	Earthwork cutting	C.yd.	721
2	Earthwork embankments with consolidation	,,	7,491
3	Consolidation charges for using the earth got from cutting bund.	,,	721
4	Turfing	S.yd.	9,043
5	Gravel backing	C.yd.	124
6	Filling in small boulders and jelly behind revetment for bringing the dips and holes to an uniform slope.	,,	286
7	Removing and resetting old stone work with new jelly ...	,,	804
8	Collecting, carting, stacking, filling and wedging new jelly for old revetment.	,,	140
9	New stone work carting from 3 to 4 miles bund ...	,,	669
10	Clearing jungle over revetment and on front and rear slopes of bund.	Grades	35
11	Sopanum Dressed new stone slabs	S.ft.	292
12	Burnt brick in surki mortar	C.ft.	142
13	Surki plastering	Sqr.	3·02
14	Removing, refixing, painting and figuring the old grade stone	Grade	39
15	Supplying, fixing and painting new grade stones ...	...	2
16	Index stone	No.	41
17	Removing, refixing, painting and figuring the old registered number stone.	,,	1
18	Do do B. M. stone	,,	2
19	Collecting, cutting and spreading gravel over bund from a distance of about a mile.	C.yd.	82
20	Providing earthern platform at convenient intervals on tank bund to await carts being crossed each other freely.	Lumpsum	Rupees
	SLUICES.		
1	Repairing the front and rear cisterns of No. 1 sluice and also raising the top slabs and gibbets and pillars of both the pillars.	Lumpsum	Rupees
	WASTE WEIR.		
1	Earthwork cutting and refillnig with consolidation ...	C.yd.	81
2	Removing and refixing the top slabs, the joggles on surki mortar.	S.ft.	270
3	Dismantling brick masonry	C.ft.	145
4	Burnt brick in surki mortar	,,	2,134
5	Surki plastering	Sqr.	13·17
6	Filling small boulder...	C.yd.	18
7	Old stone work with new jelly	,,	74
8	New stone work	,,	7
9	Jelly filling to old apron	,,	9
10	Earthwork with consolidation	,,	115
11	Turfing	Sqr.	192

R. W. SCALDWELL,
Executive Engineer.